Abstract Notification dated 3rd September 1938.

The attention of firms dealing in Printing and Supply of Stationery articles is invited to this Office Notifications Nos. G. N. 29 and 30, dated the 3rd September 1938, published on pages 1545-1562 of Part VI of the *Mysore Gazette*, dated 8th September 1938, in connection with the printing and supply of books, forms, etc., and stationery articles required by this department.

S. G. FORBES,
Chief Electrical Engineer.

OFFICE OF THE SUPERINTENDING ENGINEER, BANGALORE.

Notification dated 9th September 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, upto 3 P.M. on the 30th September 1938, for constructing one unit of Double Block of Operators' Quarters, with one Unit of Latrine at Nanjangud Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of December 1938.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Operators' Quarters at Nanjangud Town," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Charges on account of water, scaffolding materials implements for setting out, barricading, clearing site, supply of workmen, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

Abstract for constructing one unit of Double Block of Operators' Quarters including one Unit of Latrines at Nanjangud.

Item No.	Description of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation and filling in basement ..	C.yd.	0 4 0	53	
2	Stone jelly concrete in lime mortar	C.ft.	0 4 0	597	
3	Size stone in clay foundation and basement with bond stones as per specifications	,,	0 4 0	1,079	
4	Burnt brick in clay superstructure	,,	0 3 6	1,946	
5	Burnt brick in mortar do	,,	0 4 6	746	
6	Supplying and fixing burnt stone slabs, 6" thick, and dressed	S.ft.	0 9 6	249	
7	T.W. doors with battened shutters 1" thick with bolts, hinges, etc., completed, as per drawing ..	,,	1 6 0	280	
8	T.W. windows with battened shutters 1" thick with iron bars, fixtures, etc., complete as per drawing	,,	1 6 0	116	

Item No.	Description of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
9	Supplying and fixing T.W. shelves with two planks and shutters with locking, etc., complete ..	S.ft.	1 6 0	96	
10	T.W. wrought and put up with two coats of wood oiling	C.ft.	5 0 0	51·55	
11	T.W. eave-board 9″ deep including fixing ..	R.ft.	0 10 0	149	
12	Roofing with first class Mangalore tiles on T.W. reepers 2″×1″ including wood oiling to the reepers	Sqr.	28 0 0	12·28	
13	Mangalore ridge tiles set in mortar including cement pointing	R.ft.	0 10 0	78	
14	Providing and fixing rolled steel joists (Tata's tested)	Cwt.	14 0 0	6·36	
15	Boxing girders with brick in cement and plaster complete	R.ft.	1 0 0	20	
16	R. C. brick-nogged terrace with brick in surki mortar with wedge-shaped R.C. joists, surki complete, two layers of flat tiles, plastered, etc., complete, as per specification	Sqr.	60 0 0	3·74	
17	Parapet wall as per design	R.ft.	0 12 0	60	
18	Cornice as per design all round	,,	0 6 0	63	
19	Flooring with 1″ thick cement concrete on 3″ lime concrete with ½″ thick cement plaster on top and coloured red	Sqr.	22 0 0	9·00	
20	Plastering with lime mortar, two coats	,,	3 0 0	50·00	
21	Cement pointing with thread lines	,,	2 8 0	2·20	
22	White and colour washing, two coats	,,	0 4 6	52·20	
23	Rain water down pipes of 3″ dia. of plain galvanised iron sheet, 22-BWG fixed with clamps, etc., complete, including painting	R.ft.	0 8 0	65	
24	Mortar bands including plastering, etc., complete	,,	0 5 0	24	
25	Chocolate painting, two coats	Sqr.	3 12 0	13·33	
26	Expanded metal 3″×1½″ mesh with ⅛″ strand with T.W. frame, including door-way, complete ..	S.ft.	0 10 0	123	
27	Providing chimney, etc.	L.S.	20 0 0	..	
28	Constructing sinks, complete with outlet pipes ..	No.	5 0 0	2	
29	Providing and fixing stone-mortar pestle ..	,,	8 0 0	2	
30	Providing and fixing copper handas in bath rooms	,,	15 0 0	2	
31	Levelling ground	L.S.	15 0 0	..	
	FOR CONSTRUCTING THE LATRINE.				
1	Earthwork excavation for foundation and filling in basement	C.yd.	0 4 0	4	
2	Stone in clay foundation and basement	C.ft.	0 4 0	130	
3	Burnt brick in lime mortar	,,	0 4 6	196	
4	Chunam plastering, two coats	Sqr.	3 0 0	4·91	
5	Cement pointing with thread lines	,,	2 8 0	0·56	
6	White and colour-washing, two coats	,,	0 4 6	5·47	
7	Cement plastering, ½″ thick	,,	9 0 0	0·79	
8	Tar-washing, two coats	,,	2 8 0	0·63	
9	Flooring with 1″ cement concrete and ½″ cement plaster over a bed of 3″ lime concrete ..	,,	22 0 0	0·38	
10	Fixing outlets and constructing drains, etc. ..	L.S.	10 0 0	..	
11	Providing galvanised iron sheet tubs 12″×6″ of 22-BWG. complete with larring	No.	1 8 0	6	

A. C. MUNIRATHNAM,
For Superintending Engineer.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, K. G. F., CHAMPION REEFS.

Abstract Notification.

Installing Electric Pump in place of the Semi Rotary Pump for Sri Narasimharaja Hospital, Kolar.

Attention is drawn to this Office Notification dated 25th August 1938, inviting tenders for the above work, published in Part VI, Page 1562 and 1563 of the *Mysore Gazette*, dated 8th September 1938. The last date of receiving tenders is 26th September 1938, and the earnest money required is Rs. 30.

R. PRASAD,
Superintendent.